

## **COPYRIGHT NOTICE**

This geotechnical log and its associated data (the Document) is licensed by the Queensland Department of Transport and Main Roads under the [Creative Commons Attribution 4.0 Licence](#) (CC BY 4.0). When reusing the Document, in whole or in part, please attribute the Department as follows: "*(c) State of Queensland (Department of Transport and Main Roads) 2020, licensed under the CC BY 4.0 Licence*". This licence does not apply to the Queensland Government logo or trademarks.

## **LIMITATION OF LIABILITY**

The CC BY 4.0 Licence contains a comprehensive Disclaimer of Warranties and Limitation of Liability. In addition, please note that this Document was prepared for Departmental use only. Reuse of the Document by anyone for any other purpose could result in error and/or loss. You should obtain professional advice before making decisions based on the contents of the Document.

When reproducing any part of this Document, you must also reproduce this limitation of liability notice in addition to the italicised attribution statement above.

Retrieved from the Queensland Geotechnical Database <http://qgd.org.au/>



# ENGINEERING BOREHOLE LOG

FOR GEOTECHNICAL TERMS AND  
SYMBOLS REFER FORM F:GEOT 017/6-2010

BOREHOLE No BH15  
SHEET 1 of 2  
REFERENCE No H11025

PROJECT Moreton Bay Rail Link  
LOCATION Halpine Lake Bridge, Bridge 9, Ch.6100 COORDINATES 502912.9 E; 6986533.2 N  
PROJECT No FG5921 SURFACE R.L. 16.90m PLUNGE \_\_\_\_\_ DATE STARTED 5/5/11 GRID DATUM MGA94 Zone 56  
JOB No 250/120/3 HEIGHT DATUM AHD BEARING \_\_\_\_\_ DATE COMPLETED 5/5/11 DRILLER R&D Drilling Pty Ltd

DEPTH (m)	R.L. (m)	AUGER CASING WASH BORING CORE DRILLING	RQD ( ) %	CORE REC %	SAMPLE	MATERIAL DESCRIPTION	LITHOLOGY	USC WEATHERING	INTACT STRENGTH	DEFECT SPACING (mm)	GRAPHIC LOG	ADDITIONAL DATA AND TEST RESULTS	SAMPLES TESTS
0	16.90					<b>Clayey SAND</b> Mottled red, moist, loose.						Based on Driller's logs only	
1	15.90				A	<b>Sandy CLAY (Residual)</b> Light grey and yellow scattered with orange mottles, iron stained, moist, soft to stiff. High plasticity.						0,1,1 N=2	SPT
2					B	Sand fraction is fine to medium grained. Nodule and sand content increasing with depth; trace of stiff, angular to subangular gravel.	(CH)					3,8,11 N=19	SPT
3	13.90				C	<b>Clayey SAND (Residual)</b> Grey white, slightly moist, medium grained, medium dense.						6,9,13 N=22	SPT
4					D	Quartz feldspathic sand. Medium plasticity.						6,10,17 N=27	SPT
5					E	Orange iron stained bands throughout.	(SP-SM)					8,12,16 N=28	SPT
6					F							10,12,17 N=29	SPT
7	9.90				G	<b>SANDSTONE</b> Medium to fine grained, massive, poorly cemented, sedimentary rock mainly comprising sand-sized particles. HW: Mottled grey with bands of red, fine grained, low strength.						13,30/75mm N>50	SPT
8			(43)			Iron stained bands throughout.	HW					Silty CLy band	
9	7.45		100 (95)			Defects: Generally rare.							
10			100			<b>MW:</b> See over	MW						

REMARKS \_\_\_\_\_

LOGGED BY  
BW / JSM

# ENGINEERING BOREHOLE LOG

FOR GEOTECHNICAL TERMS AND  
SYMBOLS REFER FORM F:GEOT 017/6-2010

BOREHOLE No BH15  
SHEET 2 of 2  
REFERENCE No H11025

PROJECT Moreton Bay Rail Link  
LOCATION Halpine Lake Bridge, Bridge 9, Ch.6100 COORDINATES 502912.9 E; 6986533.2 N  
PROJECT No FG5921 SURFACE R.L. 16.90m PLUNGE      DATE STARTED 5/5/11 GRID DATUM MGA94 Zone 56  
JOB No 250/120/3 HEIGHT DATUM AHD BEARING      DATE COMPLETED 5/5/11 DRILLER R&D Drilling Pty Ltd

DEPTH (m)	R.L. (m)	AUGER CASING WASH BORING CORE DRILLING	RQD (%)	SAMPLE	MATERIAL DESCRIPTION	LITHOLOGY	USC	WEATHERING	INTACT STRENGTH	DEFECT SPACING (mm)	GRAPHIC LOG	ADDITIONAL DATA AND TEST RESULTS	SAMPLES TESTS
10	6.90		(0) 100		<b>SANDSTONE</b> <b>MW: (Cont'd)</b> Yellow red to grey, massive, coarse grained, low to medium strength.  Contains quartz feldspathic sand in a matrix of clay cement.  Defects: - Drilling-induced fracture @ 5-10° (1-4/m) - Joint @ 25° (1-2/m) - Joints @40-45° (1-2/m)							Is(50) = 0.55MPa Is(50) = 0.68MPa	x o
11			(72)										
12			100 (88)		Defect surfaces are generally closed, planar and clay infilled.  Becoming high strength below 12m.  SW Conglomeratic sandstone bands below 13.5 app. 500mm thick.	MW						Is(50) = 2.08MPa Is(50) = 1.53MPa DD = 2.18t/m³; MC = 5.8%; UCS=19.4MPa	x o UCS
13			100 (50)									Is(50) = 1.02MPa Is(50) = 1.11MPa	x o
14	2.70		100 (60)		<b>MUDSTONE</b> <b>Fine grained, laminated, sedimentary rock mainly comprising of mud-sized particles</b> <b>SW:</b> Dark brown to black, laminated, low to mainly medium to high strength.  Contains siltstone interbeds.  Defects: - Joint @ 10° - Joint @ 75°							Is(50) = 3.06MPa Is(50) = 3.42MPa	x o
15			(89)		Defect surfaces are close to medium spaced, planar, smooth, open and clay infill.	SW						Is(50) = 0.16MPa Is(50) = 0.92MPa  Is(50) = 1.93MPa Is(50) = 1.72MPa	x o x o
16			100 (87)		<b>SILTSTONE</b> <b>Fine grained sedimentary rock mainly comprising of silt sized particles</b> <b>SW:</b> Grey, fine grained, laminated, high strength.  Contains mudstone interbeds.  Defects: As above.	SW						Is(50) = 0.58MPa Is(50) = 0.78MPa  Is(50) = 0.56MPa Is(50) = 1.32MPa	x o x o
17	-0.35											Is(50) = 2.17MPa Is(50) = 5.38MPa DD = 2.45t/m³; MC = 2%; UCS=16.7MPa	x o UCS
18	-1.85		100		Borehole terminated at 18.75m							Is(50) = 2.65MPa Is(50) = 3.55MPa	x o
19													
20													

REMARKS     

LOGGED BY  
BW / JSM



<b>Project Name</b>	<b>Moreton Bay Rail Link (MBRL)</b>		
<b>Project No</b>	FG5921	<b>Date</b>	05/05/11
<b>Borehole No</b>	BH 15	<b>TMR H No</b>	11025
<b>Location</b>	Bridge over Halpine lake	<b>Start Depth (m)</b>	7.50
<b>Detail</b>	Structure	<b>Finish Depth (m)</b>	18.75
<b>Chainage</b>	Approx	<b>Submitted By</b>	BW
<b>Remarks</b>			

