COPYRIGHT NOTICE

This geotechnical log and its associated data (the Document) is licensed by the Queensland Department of Transport and Main Roads under the <u>Creative Commons Attribution 4.0 Licence</u> (CC BY 4.0). When reusing the Document, in whole or in part, please attribute the Department and author as follows: "(c) State of Queensland (Department of Transport and Main Roads) 2020, licensed under the CC BY 4.0 Licence, prepared by WSP". This licence does not apply to logos or trademarks.

LIMITATION OF LIABILITY

The CC BY 4.0 Licence contains a comprehensive Disclaimer of Warranties and Limitation of Liability. In addition, please note that this Document was prepared for Departmental use only. Reuse of the Document by anyone for any other purpose could result in error and/or loss. You should obtain professional advice before making decisions based on the contents of the Document.

When reproducing any part of this Document, you must also reproduce this limitation of liability notice in addition to the italicised attribution statement above.

Retrieved from the Queensland Geotechnical Database http://qgd.org.au/

This log has been contributed to the Queensland Geotechnical Database with the permission of WSP.

BOREHOLE ENGINEERING LOG

BOREHOLE NO.



100

SHEET 1 OF 2

Client: Project: Department of Transport and Main Roads

Gold Coast Rapid Transit

Borehole Location: Project Number:

Barney Street, Ch: 24874.5

2161016A

Date Commenced: Date Completed:

3/3/10 3/3/10

Recorded By: Log Checked By:

DS make

Drill Model/Mounting:

Drillpower Hydrapower Scout

Hole Angle: 90° Surface RL:

1.67 m AHD*

Borehole Information								Bearing: Co-ords: E 85382.13 N 60450.46 GCCC Grid*							
[_		nole						Field Material De					
ſ	1	2	3		4	5	6	7	8	9	F	10	11	12	13
	METHOD	SUPPORT	WATER	RL(m) AHD*	DEPTH(m)	FIELD TEST	SAMPLE	GRAPHIC LOG	USC SYMBOL	SOIL/ROCK MATERIAL FIELD DESCRIPTION		MOISTURE	RELATIVE DENSITY / CONSISTENCY	HAND PENETROMETER (KPa)	STRUCTURE AND ADDITIONAL OBSERVATIONS
ı	TC	С		-	0.05 0.15			XXX		ASPHALT	1				PAVEMENT MATERIALS
		o	3/03/1	- 1 - 1 0 0 1 	0.70				sw	FILL (Sandy GRAVEL): fine to coarse grained, grey-brown, fine to coarse grained sand. FILL (Gravelly SAND with SILT): medium grained, brown, fine to coarse grained, angular gravel. FILL (SAND): fine grained, dark grey with organics. 1.0 m: pale grey FILL (Clayey SAND with GRAVEL): grey-brown, fine to medium grained, medium plasticity fines, fine to medium grained angular gravel. SAND: fine grained, dark grey-brown, with shell fragments, trace organics.		X.			ESTUARINE SEDIMENTS WEATHERED ROCK
LOG GCRT_BOREHOLES.GPJ GEOTECH_24-2-2006.GDT 26/5/10				- - 3 - - - - 4	4- - - - 5- - -					pale green to grey, appears silicified, moderately weathered, low strength.					WEATHERED ROCK
Parsons Brinckerhoff Australia Pty Ltd. Version 5.1 ENGINEERING BOREHOLE LOG G					8- 	Thie b	Oreh		shou	REFER TO CORED BOREHOLE LOG			mpanying	tandard	notes
						This b	oreh	ole log	shou	lld be read in conjunction with Parsons Brinckerhoff's	ac	cco	mpanying s	tandard	notes.



CORED BOREHOLE ENGINEERING LOG

BOREHOLE NO.

RTBH18A

SHEET 2 OF 2

Client: Department of Transport and Main Roads

Project: Gold Coast Rapid Transit
Borehole Location: Barney Street, Ch: 24874.5

Project Number: 2161016A

Date Completed: Recorded By:

3/3/10 3/3/10 DS

Drill Model/Mounting: Drillpower Hydrapower Scout

Hole Angle:

90° Surface RL:

1.67 m AHD*

Date Commenced:

Log Checked By:

Drill Model/Mounting: Drilly Borehole Diameter: 75 m Borehole Information			75 mm		Bear		90	Co-	race RL: ords:	1.67 m AHD* E 85382.13 N 60450.46 GCCC Grid				
1	Bor 2	rehc	ole I	nfo 5	rmat	ion 6	7	8	Fiel	d N	laterial De	scription 11	12	
метнор -	SUPPORT		CORE RECOVERY		RL(m) AHD*	DEPTH(m)	GRAPHIC LOG	SOIL/ROCK MATERIAL FIELD DESCR	RIPTION	rhering	INFERRED STRENGTH Is(50) MPa PA	AVERAGE DEFECT SPACING mm	STRUCTURE AND ADDITIONAL OBSERVATIONS	
					1	1- 1- 2- 3- 3- 5-		COMMENCE CORING AT 6 m						
NMLC	M		100	40		,		META-GREYWACKE: fine to me grained, pale green to grey, appe silicified.		MW			 6.0 m - 8.0 m: Multiple healed fractures with quartz infill and trace Fe staining. 6.05 m: J, 45°, P, S, Fe stained 6.17, 6.26 m: J x 2, 10°, Ir, R, Fe stained 	
			100	30	5 -	7-							 6.17, 6.26 m: J x 2, 10°, Ir, R, Fe stained 6.46 m: DB, Ir, R, trace pyrite 6.53 m - 6.63 m: J, 70°, P, S, trace Fe stained 6.55 m: J, Ir, R 	
			100	6	- - 6 -	- - - 8-							6.62 m: DB 6.65 m: J, 45°, P, S, Fe stained 6.65 m - 6.84 m: J, 80°, P, S, incipient in parts, trace pyrite ? 6.92 m: J, 45°, P, S, clean 7.1 m - 7.64 m: 7 x J, 15° to 45°, P-Ir, S-R, Fe Stained	
			100		100	- - - - 9		8.5 m - 8.62 m: pale grey. END OF BOREHOLE AT 9.00 m					7.85 m - 7.9 m: Non intact core, Fe stained, 7.9 m - 8.0 m: Non intact core 8.02 m: J, 45°, P, S, clean 8.14 m - 8.28 m: Quartz vein, sub vertical irregular, 5-20 mm, Fe stained 8.33 m - 8.6 m: Non intact core 8.65 m, 8.89 m: J, 60-90°, P, S, clean	
					- - 8								Limit of Investigation * Horizontal and vertical data determined by Ground Survey	

REPORT OF PHOTOGRAPHS



Borehole number:

Sheet

RTBH18A

of

Department of
Client: Transport and Main Roads

Project: Gold Coast
Project: Surface RL: 1.67 m AHD Inclined length: -

Rapid Transit Surface RL: 1.67 m AHD Inclined length: –

Borehole location: Ch: 24869.3 Hole angle: 90 ° Drill model/mounting: Hydrapower Scout

Project number: 2161016A Bearing: – Borehole diameter: 75 mm

